

Substitute Specification

DEVICE AND METHOD FOR GENERATIVE MANUFACTURE OF A THREE-DIMENSIONAL OBJECT

Field Of The Invention

The present invention relates to a device and a method for generative manufacture of a three-dimensional object.

Background Of The Invention

A device for generative manufacture of a three-dimensional object by selective laser sintering is known, for example, from EP 0 734 842 A. There a first layer of a powdered material is applied to a base detachably connected to a lowerable carrier and irradiated at the points corresponding to the object, so the material sinters together there. Then the carrier with the base is lowered and a second layer is applied to this first layer and again selectively sintered, the second layer therein being connected to the first layer. In this way the object is formed in layers. When the formed three-dimensional object is complete, together with the base it is taken manually out of the device. This removal limits productivity, as during removal no further object can be manufactured.

The object of the invention is to provide an improved device for generative production of a three-dimensional object with which productivity can be increased and an improved method for generative production of a three-dimensional object with which productivity can be increased. Summary Of The Invention

The present invention provides a device for generative manufacture of a three-dimensional object, with a construction area, in which the object is manufactured and a control system (9) which is constructed in such a way that it can control the execution of the following steps:

- a) manufacture of an object,
- b) removal of the manufactured object from the construction area,
- c) repeating steps a) and b), characterised by a conveying device (18, 31, 32) for unloading and loading the construction area with a construction platform (3) for carrying the object to be manufactured.

The present invention also provides a method for generative manufacture of a three-dimensional object with a device with the steps:

- a) manufacture of an object in a construction area of the device,
- b) removal of the manufactured object from the construction area and
- c) repeating steps a) and b),
 wherein steps a) to c) are carried out automatically,
 characterised in that before each step a) the following step
 d) is carried out:
 - d) automatic loading of the construction area with a construction platform (3) for carrying the object to be constructed.

Further embodiments of the invention provide a device having one or more of the following features:

- a) the control system is constructed in such a way that it can control in step a) loading the construction area with the construction platform (3) and in step b) unloading the construction platform (3) with the manufactured object from the construction area;
- b) a feed device (16) for feeding the construction platform (3) to be loaded into the device to the conveying device (18, 31, 32) and a removal device (17) for removing a construction platform (3) to be unloaded from the device from the conveying device (18, 31, 32);
- c) the feed and removal devices (16, 17) are connected to the conveying device (18, 31, 32) via switch gear (19):
- d) a travelling actuating element (4) for setting the position of the construction platform (3) in the construction area and a connecting device (40) for connecting the construction platform (3) to the actuating element (4);
- e) a connection final control element for actuating the connecting device (40);
- f) the connection final control element (40) is the actuating element (4);
- g) the connecting device (40) is provided on the construction platform (3);
- h) a construction frame (1) surrounding the construction platform (3) is provided, which is loaded and unloaded into or from the construction area together with the construction platform (3);
- i) a mounting (13') and a coupling device (20) for coupling the construction frame (1) to the mounting (13') during loading and for uncoupling the construction frame (1) from the mounting (13') during unloading;

- j) the coupling device (20) has a coupling element (27) which brings the construction frame (1) in the coupled state into connection with the mounting (13');
- k) a coupling final control element for coupling and/or uncoupling;
- 1) the coupling final control element is the actuating element (4) for setting the position of the construction platform (3) in the construction area:
- m) the coupling element (27) is biased and the coupling device (20) has a carrier (30) connected to the coupling final control element, which can be moved by the coupling final control element in such a way that it moves the coupling element (27) against the bias;
- n) the coupling device has an adjustable positioning element (23, 24), with which the relative position of the construction frame (1) to the mounting (13') in the coupled state can be set;
- o) an application device (8) for applying hardenable material on to the construction platform (3) and a hardening device (6, 7) for the selective hardening of the applied material;
- p) the device is constructed in such a way that the object can be manufactured in layers; and
- q) the control system is constructed in such a way that after the manufactured object has been removed system maintenance of the device is carried out automatically.

Additional embodiments of the invention provide methods having one or more of the following features:

1) in step d) the construction platform (3) is connected to a travelling actuating element (4) for setting the position of the construction platform (3) in the construction area;

- 2) in step d) the construction area is automatically loaded with the construction platform (3) and with a construction frame (1) surrounding the construction platform (3);
- 3) in step d) the construction frame (1) is connected to a mounting (13') of the device;
- 4) in step b) the construction platform (3) is removed together with the object manufactured on it;
- 5) the object is manufactured in layers; and
- 6) after the manufactured object has been removed, system maintenance of the device is carried out automatically.

Further features and advantages of the invention emerge from the description of embodiment examples using the figures.

Brief Description Of The Drawings

- Fig. 1 shows a schematic sectional view of a device for manufacturing a three-dimensional object.
- Fig. 2 shows a perspective illustration of the device for manufacturing a three-dimensional object.
- Fig. 3 shows a sectional view of a part of the device for manufacturing a three-dimensional object from Fig. 2, in which the construction frame is coupled to the mounting.
- Fig. 4 shows the sectional view according to Fig. 3, in which the construction frame is uncoupled from the mounting.
- Fig. 5 shows the sectional view according to Fig. 3 without construction frame put in.
- Fig. 6 shows an enlarged partial view of region A of Fig. 3.

Detailed Description Of The Invention

As can best be seen from Fig. 1, the device for manufacturing a three-dimensional object has a construction frame 1, open to the top and the bottom, with circular, square or rectangular cross-section with an upper edge 2. In the construction frame a construction platform 3 is provided, connected to a vertical drive 4. The construction platform 3 can be moved up and down in the vertical direction via the vertical drive 4. On the outer edge of the construction platform 3 a seal 5 provided, which seals the gap between the construction platform 3 and the construction frame 1. Above the upper edge 2 is arranged a hardening device in the form of a laser 6 and a deflection mirror 7. Further provided is another application device 8 for applying the material to be applied to the construction platform 3. The laser 6, the deflection mirror 7, application device 8 and the vertical drive 4 are controlled by a control system 9. In the illustration in Fig. 1 a formed object 10 is drawn in, surrounded by non-hardened material 11. The construction frame 1 and the construction platform 3 together form a mobile container 12.

The device shown in Fig. 1 is arranged in a housing 13, shown in Fig. 2. This housing 13 has on its front face a door 14, which opens and closes automatically. In the housing 13 a construction area is provided, in which the object is manufactured. The mobile container 12 is arranged in this construction area during manufacture. Further provided is a rail system 15, connected to the housing 13, with a conveyor drive, not shown, e.g. a chain drive. With this rail system 15 an empty mobile container 12_1 , 12_2 is conveyed into the device for manufacturing a three-dimensional object and a full mobile

container 12₃, in other words a mobile container in which a formed object is contained, is conveyed out of the device. For this the rail system 15 has a feed section 16, a removal section 17 and a connecting section 18, connected to the device. The feed section 16, the removal section 17 and the connecting section 18 are connected to one another via switch gear 19. The feed section 16 and the removal section 17 are connected to a store, not shown, in which the empty mobile containers and the full mobile containers are kept.

As well as the rail system 15, the device contains a coupling device 20 for coupling the mobile container 12 to a mounting 13' of the housing 13 and for uncoupling the mobile container 12 from the mounting 13'. Fig. 3 shows a sectional view through the corresponding part of the mounting 13' of the housing 13, wherein a state is shown in which the mobile container 12 is coupled to the mounting 13'. As shown in Fig. 3, the construction frame 1 has in each case a projection 21, 22, projecting outwards at its lower end on both sides. On each of these projections 21, 22 an adjustable positioning element 23, 24 is provided in each case. The positioning elements 23, 24 also have in each case the effect of a stop. The length of the adjustable positioning elements 23, 24 can be set in the direction of the movement of the vertical drive 4. The mounting 13' has abutment faces 25, 26, with which the adjustable positioning elements 23, 24 are in contact in the coupled state of the mobile container 12. As can best be seen in Fig. 4, the abutment faces 25, 26 and the adjustable positioning elements 23, 24 can be constructed in such a way that in the coupled state of the mobile container 12 they engage in one another by positive locking. As can be seen from Fig. 3, the mobile container 12 is supported with its lower

end on a plate 27, which is connected to the mounting 13' by springs and biased in such a way that the mobile container 12 seen in Fig. 3 is pushed upwards in such a way that the adjustable positioning elements 23, 24 are in engagement with the abutment faces 25, 26. The plate 27 is constructed in such a way that it has a recess 29 in the middle, through which the vertical drive 4 is guided. On the vertical drive 4 a carrier 30 is mounted, which, as shown in Fig. 3, is arranged above the plate 27. The carrier 30 is constructed in such a way that it is larger than the recess 29 of the plate 27. Therefore when the vertical drive 4 moves downwards the carrier 30, as shown in Fig. 4, comes into contact with the plate 27 and takes it with it in the movement downwards against the force of the spring.

Further provided, as shown in Fig. 3, are two circulating chains 31, 32, arranged below the plate 27. On the underside of the projections 21, 22 of the construction frame 1 in each case a chain coupling element 33, 34 is mounted. The chains 31, 32 and the chain coupling elements 33, 34 are arranged with respect to one another in such a way that when the construction frame 1 moves downwards the chain coupling elements 33, 34 come into contact with the chains 31, 32, as shown in Fig. 4.

The device further has another locking device 40, as shown in Fig. 6. Fig. 6 is a detail enlargement of area A from Fig. 3, wherein the plate 27, the springs 28 and the carrier 30 are not drawn in. On the underside of the construction platform 3 a connecting piece 41 is mounted, on which a rocker arm with a first leg 43 and a second leg 44, extending perpendicular to it, is carried so as to be rotatable over the connecting area

of the two legs 43, 44 at the crossing point of the longitudinal axes of the legs. The open end of the second leg 44 is rotatably connected to a locking rod 45, which is guided in a guide 46 in such a way that the locking rod 45 in the inserted state of the mobile container 12 can be moved forwards and backwards only perpendicular to the direction of movement of the vertical drive 4, as indicated by the double arrow A in Fig. 6. The guide 46 is connected to the construction platform via a connecting element, not shown. The front end 47 of the locking rod 45, pointing away from the open end of the second leg 44, is constructed as tapering. An annular recess 48, formed corresponding to the front end 47 is provided on the vertical drive 4. A rotatably carried roller 49 is provided at the open end of the first leg 43 of the rocker arm 42. In the position of the construction platform 3 shown in Fig. 6 the roller 49 is in contact with an unlocking projection 50 of the construction frame 1. Between the rocker arm 42 and the connecting piece 41 is arranged a torsion spring 41, which biases the rocker arm in such a way that the locking rod 45 is moved towards the vertical drive 4. rocker arm 42, the unlocking projection 50 and the locking rod 45 are arranged in such a way that on further movement of the vertical drive 4 downwards in the state shown in Fig. 6 the unlocking projection 50 presses the first leg 43 of the rocker arm 42 via the roller 49 upwards against the force of the spring of the torsion spring 51, so the locking rod 45 in Fig. 6 is moved to the left, whereby the engagement of the front end 47 with the recess 48 is released.

The operation of the device will now be described. It is therein assumed that a construction platform 3 and a construction frame 1 are already contained in the device or in

the construction area. First the construction platform 3 is positioned in the construction frame 1 in such a way that it is positioned below the upper edge 2 of the construction frame 1 by a predetermined layer thickness. Then by means of the application device 8 a layer of the material to be hardened is applied to the construction platform 3 and then selectively hardened at the desired places with the hardening device. After that the construction platform is lowered by a desired layer thickness and a further layer of material is applied. This is again selectively hardened and therein connected to the lower layer of material. This is continued until the object to be manufactured is complete. Several objects in succession and/or on top of one another on the construction platform 3 can also be manufactured in a construction process of the sort described. Then the construction platform 3 is moved into the position shown in Fig. 3. The control system 9 controls the vertical drive 4 further in such a way that it travels from the position shown in Fig. 3 further downwards. In this way the carrier 30 comes into contact with the plate and takes it with it when the vertical drive moves downwards against the force of the spring of the springs 28. In this way the mobile container 12, which is located on the plate 27, is also moved downwards. Thus the engagement between the adjustable positioning elements 23, 24 and the abutment faces 25, 26 is released. This movement of the vertical drive 4 downwards is continued until the chain coupling elements 33, 34 reach engagement with the chains 31, 32, as shown in Fig. 4. Simultaneously by this movement of the vertical drive 4 downwards the first leg 43 of the rocker arm 42 is pressed against the unlocking projection 50 of the construction frame 1, shown in Fig. 6, whereby the first leg 43 is moved towards the construction platform. In this way the locking rod 45 seen

in Fig. 6 is moved to the left and the engagement between the front end 47 of the locking rod 45 and the recess 48 is released. Therefore the construction frame 1 is uncoupled from the mounting 13' and the construction platform 3 separated from the vertical drive 4. Now by means of the control system 9 the automatic door 14 (Fig. 2) is opened and the chains 31, 32 triggered, whereby the full mobile container 12 is conveyed out of the device (Fig. 5). The switch gear 19 has previously been set in such a way that the full mobile container 12 is conveyed to the removal section 17. From there the full mobile container 12 is conveyed to the store. After that the switch gear 19 is re-set in such a way that the feed section 16 is connected to the connecting section 18. Via this connection an empty mobile container 12_1 is now conveyed into the machine. The vertical drive 4 is now moved upwards by the control system 9. In this way in reverse order the empty mobile container 12_1 is coupled to the mounting 13' of the housing 13, as shown in Fig. 3, and the construction platform 3 is locked to the vertical drive 4, as shown in Fig. 6. The control system 9 now carries out all the activities necessary for starting a new construction process. This comprises, for example, providing the geometrical data for the object to be manufactured and checking the state of the device. checking comprises, for example, a check of whether there is still sufficient material in the device and checking the hardening device. Based on the result of this checking, for example topping up material from an external storage vessel, the hardening device and/or carrying calibration of the hardening device are controlled by the control system 9. After that the control system 9 starts a new construction process and a new object is now formed on the construction platform 3 of the empty mobile container 12_1 . The

steps described are all carried out automatically by means of the control system 9.

advantage of this embodiment is that coupling and uncoupling of the construction frame 1 to the mounting 13' of the housing 13 is carried out by the movement of the vertical drive 4. This saves having an additional Furthermore, the actuating force for the locking construction platform 3 and vertical drive 4 is also derived from the movement of the vertical drive 4. A solution of this kind has the advantage, in view of the raised temperatures occurring in this area of the construction frame, typically between 100 and 150°, when certain materials are used, such as e.g. synthetic powder, that no actuator is subjected to these temperatures. In addition there is no need for sensors or switches, which promotes simplicity and therefore reliability.

In an alternative embodiment it is possible to generate the lifting movement required for coupling the construction frame 1 to the mounting 13' of the housing 13 and for locking the construction platform 3 to the vertical drive 4 by an additional actuator. An additional actuator can also be provided in each case for each of these movements.

In a further development of the invention the housing 13 of the device bordering on the front side has a further door on one of the side walls or on the back. The rail system is then connected to this door and provided either at the side of or behind the machine. This has the advantage that the machine can be loaded manually through the door 14 on the front face and automatically via the rail system via the side or rear door. Also in a further development the control system is

constructed in such a way that after the manufactured object has been removed system maintenance of the device, comprising, for example, cleaning the blades of the application device, cleaning the optics of the laser system and/or re-calibration, is carried out automatically.

A device and a method have been described in which the object is manufactured in layers by means of controlled action of a laser beam at points in each layer corresponding to the cross-section of the object. Devices and methods of this kind are, for example, a laser sintering device or a stereolithography device and the associated methods. The invention is not, however, restricted to these. Any device and any method can be provided in which the object to be manufactured is formed generatively, i.e. the object is formed by controlled adding of construction material. For example, a device can also be provided in which an object is manufactured by hardening in layers of a powdered material by means of an adhesive.

A decisive point of the present invention is that the control system 9 controls the manufacture of one or more objects, the unloading of this or these object(s) from the construction area of the device, the execution of the activities for a further construction process, forming one or more further objects, the unloading of this or these object(s), etc. in such a way that this is carried out fully automatically. In this way a fully automatic sequence of several construction processes is enabled by generative manufacturing methods. Furthermore, no manual activities are required and the productivity of the device or the method is increased.

In the embodiments described loading the construction area of the device with an empty mobile container 12_1 , 12_2 , forming the object and unloading from the mobile container 12_3 with the object formed therein from the construction area is controlled in such a way that it is carried out automatically. It is also possible, however, for only the construction platform 3 to be replaced automatically. This is particularly the case with the kind of devices for generative manufacture or manufacture in layers of a three-dimensional object which have a construction frame rigidly connected to the machine or which have no construction frame. A device without construction frame is, for example, a device for the FDM method (FDM = fused deposition modelling), described for example in US 5 121 329.

Furthermore, in a further embodiment it is also possible that only the manufactured object is unloaded from the construction area of the device and afterwards a further object is manufactured which is again unloaded.

Furthermore, on removal from the construction area the manufactured objects can be put into a different area of the device and later removed manually or automatically from the device.

Abstract Of The Disclosure

A device and a method for generative manufacture of a threedimensional object are provided in which

- a) manufacture of an object in a construction area of the device,
- b) removal of the manufactured object from the construction area and
- c) repeating steps a) and b) are carried out, wherein steps
- a) to c) are carried out automatically.